

	NW 6th Ave and NW Norwood St (SR-14 Exit 12)	NE 35th Ave and Pioneer Street (SR-501)	SR 14 Roundabout (Exits 16 & 17)	NE Lake Road and NE Everett Street (SR-500)
Cost for Construction	\$2.1 Million	\$2.3 Million	\$4.4 Million (For Two Roundabouts)	\$5.9 Million
Year	2016	2017	2019	2020
Surfacing	Asphalt	Asphalt	Asphalt	Concrete
Project Area	2.2 Acres	2.4 Acres	4.8 Acres	4.5 Acres
Project Constraints - Permitting	None	None	Low	High
Project Constraints - Utilities	Minimal	Minimal	Minimal	High
Terrain	Mostly Flat	Flat	Mostly Flat	Moderate
Grading	\$\$\$	\$	\$	\$\$\$\$
Utility Upgrades	\$\$	\$\$	\$	\$\$\$
Pedestrian/Bicycle	\$\$	\$	\$	\$\$\$